

Wrong-Way Driving Detection Systems Update

Kent Thurston Adam Lough, P.E.

June 2024

WWD Task Force

Task Force Members:

- Robert Miles & Lisa Zundel (Leadership Advisors)
- Adam Lough & Tyler Laing (Co-Chairs)
- Grant Farnsworth & Mark Taylor (Traffic Management)
- Matt Luker (Traffic & Safety)
- Dan Snell & Kent Thurston (Consultant Support)



Outline

Wrong-Way Driving Update:

- How we got where we're at today?
- System Selection
- Carmanah System
- Current and Future Installations
- Safety Benefits
- Next Steps







UDOT WWD Presentation at WSRTC 2021

- UDOT spent \$500K to install thermal imaging equipment at 37 locations statewide.
- This equipment was for wrong way data collection only.
- This system did not trigger driver feedback devices.
- The data led to many signing, striping, and signal head adjustments.
- Detection had way too many false calls for accurate alerting.
- There were a lot of lessons learned from the deployment of these cameras.






Task Force Outreach

- State of Florida DOT
- State of Arizona DOT
- State of Texas DOT

- Product Presentations





TAPCO System Details















WWD Detection & Alert Systems Tests Results

Winner between systems

	Tapco	Carmanah
Install Ease	Y	Y
Fine Tuning		Y
Maintenance		Y
Sensitivity	Y	
Less False calls		Υ




TAPCO Pros:

- LegendViz backlit signs
- TAPCO does all setup
- Cloud-based alert software (BlinkLink)
- Product support
- V2X capability

TAPCO Cons:

- Maintenance package \$\$\$
- Very proprietary, not modular





Carmanah Pros:

- No Licensing Fees
- Device configuration flexibility
- Dual mode detection (radar & IR)
- V2X capability

Carmanah Cons:

- UDOT network/server reliant
- Solar sizing by location
- Limited maintenance package



WW400 System Operation

WAY



WAY



Status of \$2.5M approved by Commission

Operating

- 22 locations fully operational
- 1 locations in construction
- 7 locations in design







Cabinet



POE Surge



LED Sign Board









Breaker

A/C to D/C Transformer

DC Fuses





Detection pole (front)



Detection pole (front)



Detection pole (Detection)





Radar and Intersection Camera



Flood light and LED flashing sign



Freeway Camera





Solar flashing sign with RRFB




Flashing sign with RRFB



RRFB and LED Solar cabinet



Equipment Setup (580)






Equipment Setup (Camera)





Equipment Setup (Radar)








First draft

Prior to field installs

After field lessons











First draft






Prior to Field Installs






After Field Lessons











https://maps.app.goo.gl/wS CzQJqXn2JFbSdT8



https://maps.app.goo.gl/ArU2JEE8uVdXd3ax5








https://maps.app.goo.gl/vLSGS7xPvFwsoLma9






https://maps.app.goo.gl/nd qDBEn648VEy6GKA




Other design findings


- Grade of ramp
- Horizontal curvature of ramp
- Length of ramp
- Width of ramp
- Trees/brush and signage























































- Vendor cables vs contractor cables
- Access to pole cabinet
- Pole type
- Height and angle of devices





Vendor cables vs Contractor Cables



- Comes as a set
- Set cost
- Contractor cables
 - Adjustable length
 - Faster repair (no finger pointing on failure)
 - Pay for what is used





- Access to pole cabinet
 - Back of cabinet
 - o Bottom of cabinet running two conduits





- Pole typeLuminaire vs Ped








Setup on a ped pole







Pole typeLuminaire vs Ped





- Height and angle of devices
 - Height
 - Started at 16' above stopbar
 - Ended 30' above roadway by pole

 - Angle (moving pole back to 450')
 Started at parallel with stopbar
 Ended -2 degree parallel with roadway
 exceptions (overhead signs and things that reflect oncoming traffic)


https://maps.app.goo .gl/J6D2mkcqktCQ9o 757




Current UDOT Projects Installing WWD Detection

Current UDOT Projects

- PIN 15684 Shepard Ln Interchange rebuild
- PIN 15153 Dry Creek Parkway Interchange







Safety Benefits

3 month result chart





Safety Benefits

Safety Analysis at 23 Locations


- 32 WWD Crashes (6 severe) between Jan 2010 Jun 2023
- New systems estimated to avoid 30 WWD crashes in 20 years
- Total benefit: \$20 million
- Benefit/Cost Ratio: 4.5





Next Steps

- Adopt New Standard Drawing & Specs
- Continue Deployment of Carmanah Systems
- Transition Maintenance to Fwy Ops Group
- Integrate Alerts into Active ITS ATMS
- Gather Results/Data of Effectiveness
- Pursue Additional Funding for Deployments







Questions

Adam Lough (alough@utah.gov)
Kent Thurston (kthurston@utah.gov)